BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/04/2014-15 Dated: 31-10-2014

APPROVED TENDER SCHEDULE –'B'

Item No: 82

Name of Work:-Asphalting to roads in Narayanappa layout beside GKVK layout in ward no:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H SURESH	
				Rate	Rate in Words
1	KSRRB 500-3 Scarifying existing stone metal layer upto 75mm thic along with their bituminous surface picking up scarified materials and staking of old serviceable maerials with lead of 100 m sequential spreading of the salvaged aggregates with fresh agrreates on prepared base and consoliodating as per water bound macadam specificaions indluding cost of all labour HOM of machineries complete as per specification	Cum	2001.00	82.10	Rupees eighty two and paise ten only
2	KSRRB 300-1,Earth work excavation by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(Item no19.1,Page no138,PWD SR 2014-15)	Cum	325.90	74.84	Rupees seventy four and paise eighty four only
3	KSRRB M 400 - 17 Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density Material complete as per specification MORTH specification No 406 SR 2014-15 Page No 154 Item No 20 18	Cum	429.63	1424.17	Rupees one thousand four hundred twenty four and paise seventeen only
4	KSRRB M500-6,Providing and applying primer coat with S.S.bitumen emulsion on prepared surface of granular base such as WBM,WMM including cleaning of road surfase and spraying primer at the rate of .60kg/Sqm using mechanical means complete as per specifications. MORTH SpecificationsNo502 (ITEMNO21.6,Page no157,PWD SR 2014-15)	Sqm	4498.00	34.80	Rupees thirty four and paise eighty only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri.H SURESH	
				Rate	Rate in Words
5	KSRRB M500-18.Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading,premixed with bituminous binder and filler,transporting the hot mix to work site.laying with a paver finisher to the required grade,levell and gnment,rollingwithsmoothwheeled,vibratoryandtandemrollers to achievethedesiredcompactionasperMORTHSpecificationclauseno508completeinallrespectscomplete asperspecifications.using100120THcapacityH.M.P with sensor paver gradingI(35-40mm)with4.5%CRMB55grade(Itemno21.21.1,Pageno16D 2014-15)	Cum	62.43	10093.20	Rupees ten thousand ninety three and paise twenty only
6	KSRRB M500-19.Providing and laying semi dense bituminous concrete 40mm thick ith 100-10 TPH batch type hot mix pland producing an average output mis 75 tonnes per hour using crushed aggreates of specification grading premisec with bituminous binder at 5.4 to 5.6% mix and filler transorting the hot mix to work site laying with	Cum	80.04	10803.19	Rupees ten thousand eight hundred three and paise nineteen only
7	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/sand/kanker/Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2014-15)	Cum	325.90	67.35	Rupees sixty seven and paise thirty five only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.